

2430 E Street, N. W.
Washington 25, D. C.

29 June 1953

25X1A9A

In response to your request for advice on whether or not the Sewage Ejector Pump may be eliminated as suggested by the subcontractor for plumbing work, the following is offered for your guidance.

As of the time when the septic system was being designed, information available to the mechanical engineers indicated that terrain conditions would undoubtedly require the use of the Ejector Pump. If, upon closer examination of these conditions, it is found feasible to omit the pump, it is certainly the desire of this Office to do so. However, before reaching a decision in the matter it will be necessary for us to have the Contractor's proposal, including cost factors involved, elevations of any changes in inverts, etc. A dosing arrangement, using a hydraulic syphon, will be required.

Very truly yours,

25X1A9A